

DAILY EXCEL SIOR

DT:- 25-03-2025

## ARMY PUBLIC SCHOOL, SAMBA

Email ID [apssamba@awesIndia.edu.in](mailto:apssamba@awesIndia.edu.in)

### NOTICE INVITING TENDER

1. Sealed tenders are invited from reputed contractors approved by the Govt, having adequate experience in the similar field and have valid GST Number for extension/renovation of existing shooting range. BOQ/Scope of work of the same is uploaded in school website [www.apssamba.co.in](http://www.apssamba.co.in). Tenders documents duly signed by the vendor with firm rubber stamp accompanied with firm's covering letter, copies of contractos Registration Certificate, GST Registration Certificate, Tax Clearance Certificate and PAN/TAN of firm should be dropped in Tender box placed at **Adm Block APS, Samba** latest by **05 Apr 2025**. All documents to be self attested.

2. Vendors should read the scope of work carefully and quote the rates inclusive of all taxes, labour and delivery charges. Tender documents not accompanied with the earnest money will be rejected.

(a) Earnest Money of Rs. 52,682/- to be deposited in the form of DD in favour of **Principal Army Public School Samba**.

(b) Total period of completion of the work 3 months (After approval of CFA)

Sd/- Principal

**SCOPE OF WORK FOR EXTENSION AND RENOVATION OF EXISTING  
INDOOR SHOOTING RANGE AT ARMY PUBLIC SCHOOL, SAMBA**

**(J&K)**

**(SIZE 57 FT X 30 FT)  
ADVERTISEMENT DAILY EXCELSIOR AND THE TIMES  
OF INDIA DT 25 MAR 2025**

S.No.	Particulars of Items	Qty(Cum/Sqcm)	Unit	Rate	Amount
1.	Engagement for JCB for levelling of site	6	hours		
2.	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Exceeding 30 cm and 1.5 Mtr in depth) and for shafts, wells, cesspits and the like not exceeding 10 Sqm on plan, width upto 1.5 Mtr. Including Disposal of excavated earth upto 1 Mtr. from cutting edge disposal earth is to be levelled and neatly dressed in all kinds of soil (Code No 2.8)	40.70	Cum		
3.	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering lead upto 50 m and lift upto 1.5 m (Code 2.12) Qty @ 70% of item no - 1	20.50	Cum		
4.	Supplying and filling in plinth with fine sand under floors including, watering running consolidating and dressing complete (Code no 2.22)	41.10	Cum		
5.	Providing and Laying in position cement concrete of 1:4:8 grade (1 cement: 4 fine sand: 8 graded stone aggregate 40mm nominal size) excluding the cost of centring and shuttering. All work upto plinth level (Crushed) (Code no 4.5.9)	18	Cum		
6.	Brick work with F.P.S bricks of class designation 75m foundation and plinth in 1:6 cement mortar (1 cement: 6 fine sand) (Code no 6.1.6)	41.50	Cum		
7.	Extra for brick work in superstructure above plinth level upto floor 'V' level (By manual means)	41.50	Cum		



8.	Providing and Laying in position reinforced cement concrete 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20mm size) in beams, cantilevers, suspended floors, lintels roof slabs & shelves etc. excluding centring shuttering finishing and reinforcement all work upto plinth level. (Footings and plinth beam) (Code no 5.2.3)	19.39	Cum		
9.	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete cold twisted bars. (Code no 5.22.3)	2754.64	Kg		
10.	'A' Centring and shuttering including strutting, propping etc. and removal of form work for a Foundations, footings, bases of columns (Code no 5.9.1)	182.52	Sqm		
11.	15mm cement plaster on rough side of single or half brick wall of mix 1:6 (1 cement: 6 fine sand) (Code no 13.2.2)	413.51	Sqm		
12.	P/F of aluminium doors and windows (Complete job)	108.46	Sft		
13.	Structural steel work in built up section, trusses and framed work, including cutting, hoisting fixing in position and applying a priming coat of approved steel primer all complete.	3460.32	Kg		
14.	Providing corrugated G.5 sheet roofing fixed with polymer coated J/L hooks, bolts and nuts 8mm diameter with bitumen and G.1 limpet washers or with G.1 limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of steels complete (upto a pitch of 60 degrees) excluding the cost of purlins, rafters and trusses 0.63 mm thick.	227.21	Sqm		
15.	Distemper with dry distemper of approved brand and manufacture (two or more coats) and of required shade on new work over and including priming coat of whitening to give an even shade (Code no 13.51)	421	Sqm		

16.	Providing and Laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to I.S: 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with cement and matching pigments etc. complete size of tiles 50 x 50cm.	159.92	Sqm	
17.	Making plinth protection 50mm thick of cement concrete 1:3:6 over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and graded with fine sand including finishing the top smooth (Crushed) (Code no 16.1)	32.54	Sqm	
18.	Providing and Fixing 600 x 600mm plaster of paris (Gypsum anhydrous) ceiling tiles	1710	Sft	
19.	Providing and Fixing ceiling lights of 600 x 600mm of Jaquar made or equivalent brand	45	Nos	
20.	Providing and Fixing ceiling fans of approved brand	4	Nos	
21.	Providing and Fixing of copper wire, MCB, SPNc switches and conducting, steel box.			
				G.TOTAL

  
Principal

Army Public School  
Samba (J&K)

**SCOPE OF WORKS/SPECIFICATION FOR EXISTING  
RENOVATION OF EXISTING INDOOR SHOOTING RANGE**

**REMARKS**

SER NO	TYPE OF WORKS	REMARKS
(a)	<p><b>Construction of indoor shooting range hall</b></p> <p>Construction of indoor shooting range hall having size 57ftx30 ft With complete floor tile work , electric fitting, wood work etc i.e 1710 Sqft</p>	
(b)	<p><b>Moving Target Carrier and Controls</b></p> <ol style="list-style-type: none"> <li>1. Moving Target Carrier and Controls for 10 mtr Range Suitable for AIR Rifle and Air Pistol</li> <li>2.MAIN CONTROL UNIT</li> <li>3.MOVING TARGET CARRIER</li> <li>4.BULLET CATCHER</li> <li>5.BUTT END ASSEMBLY</li> <li>6.GUIDE ROPE 20 MTR</li> <li>7. DRIVING ROAP 20 MTR</li> <li>8.POWER SUPPLY 230V , 50Hz</li> <li>9. POWER CONSUMTION 80W Approx.</li> <li>10 TARGET SPEED 2.5m/sect- 5 to 10%</li> </ol>	

  
 Principal  
 Army Public School  
 Samba (J&K)